

STANDARD 2'-0" CURB AND GUTTER



MEDIAN CURB AND GUTTER



RUNDOWN CURB



GUTTER AT DRIVEPAD



2'-0" DEPRESSED GUTTER



ASPHALT CURB



CUT-OFF-WALL



HEADER CURB



ALLEY GUTTER



PINNED CURB TYPE I

GENERAL NOTES

1. CURB AND GUTTER REQUIRES FORMING ON ALL FACES.
2. DIMENSIONS AT ROUNDED CORNERS MEASURED TO INTERSECTION OF STRAIGHT LINES.
3. EDGES NOT SPECIFICALLY DIMENSIONED SHALL BE EDGED WITH A 3/8" EDGING TOOL.
4. ALL CONCRETE CURBING TO BE PLACED ON 6" COMPACTED SUBGRADE. 95% COMPACTION.
5. SAWCUT, REMOVE AND REPLACE 12" WIDE STRIP OF PAVEMENT BEYOND LIP OF GUTTER WHEN CONSTRUCTING CURB AND GUTTER ADJACENT TO EXISTING A.C. PAVEMENT.
6. TRANSITION FROM STANDARD CURB AND GUTTER TO EXISTING SHALL BE COMPELTED IN ONE STONE - 6' LENGTH.
7. FOR CONCRETE CURB AND GUTTER, PROVIDE CONTRACTION JOINTS AT 6' O.C. PROVIDE 1/2" EXPANSION JOINTS 36' O.C. MAX., ADJACENT TO BUILDINGS AND WALLS, AT CURB RETURNS, AND AT EACH SIDE OF DRIVEWAYS.
8. THEORETICAL FACE OF CURB OR FLOWLINE.
9. ALL CONCRETE SHALL BE AIR-ENTRAINED, MEETING THE REQUIREMENT OF STANDARD SPECIFICATION 03300.
10. ASPHALT SHALL MEET THE REQUIREMENTS OF STANDARD SPECIFICATION 02513.

REVISION IN PROGRESS

P.O. PROJECT NO.	REV	DATE	DESCRIPTION	DWN	CKD	APP
		6-15-01	UDS MODS	EG FL		

U.S. DEPARTMENT OF ENERGY
KIRTLAND AREA OFFICE — ALBUQUERQUE, NEW MEXICO
SANDIA NATIONAL LABORATORIES

CURB AND GUTTER	P.O.	T# 0849
	PROJECT NO.	CN 7140
	DRAWN BY	
	CHECKED BY	
	SNL ENGR	
CIVIL PAVING — STANDARD	DATE	9/96
	SIZE D+ / DRAWING NO. CP3001STD	SEQ.

MICROSTATION FILE
FILE NAME: CP3001STD.dgn
REFERENCE FILES:

OLD FILE NAME: 097954/A01

"Property of Sandia National Laboratories Facilities Management and Operation Center (FMOC). No duplication or alteration allowed without the expressed permission and authorization of FMOC."