

---

**DTE Energy®**



**Detroit Edison's Advanced Implementation of  
Community Energy Storage Systems for Grid Support  
(DE-OE0000229)**

**Nicholas Carlson  
Senior Engineer**

**October 20, 2011**

---



# Agenda

- CES Overview
- Project Team & Roles
- Project Phases and Schedule
- CES Operating Zones
- Communication & Control Architecture
- CES Modes of Operation
- CES Baseline & Location Selection Criteria
- CES Test Plan
- Secondary Use of Electric Vehicle Batteries
- Future Work










# Community Energy Storage

- The project is a proof of concept of an aggregated Community Energy Storage (CES) system in a utility territory; demonstrating the following capabilities:
  - Voltage/VAR Support
  - Integration renewable generation
  - Islanding during outages
  - Frequency Regulation
- Demonstrate the application of secondary-use EV batteries as CES devices. Identifying alternative applications for EV type batteries may accelerate the reduction of cost for electric vehicle batteries.
- Identify gaps, areas of improvement, and provide suggestions on how CES devices and control algorithms can be standardized to be used across the U.S.
- Provide a functional and economic analysis for using the CES system in electric utility applications.



# Project Team and Role

Project Team Members & Roles	
Team Member	Role
	<ul style="list-style-type: none"> <li>• Project lead</li> <li>• Utility participant for CES filed demo</li> <li>• Project reporting</li> </ul>
	<ul style="list-style-type: none"> <li>• CES Unit suppliers</li> <li>• Factory acceptance testing</li> <li>• Technical Support</li> </ul>
	<ul style="list-style-type: none"> <li>• CES functional testing</li> <li>• Economic analysis and reporting</li> <li>• Technical Support</li> </ul>
	<ul style="list-style-type: none"> <li>• Circuit model development for baseline</li> <li>• Reliability &amp; economic dispatch algorithm</li> </ul>
	<ul style="list-style-type: none"> <li>• Durability &amp; conditioning testing of EV battery</li> <li>• Secondary use EV battery supplier</li> <li>• Provide baseline data for EV battery</li> </ul>
	<ul style="list-style-type: none"> <li>• Investigation of regulatory issues surrounding energy storage and <u>renewables</u></li> </ul>
	<ul style="list-style-type: none"> <li>• Technical Support</li> </ul>




# Project Phases

Phase 1	Phase 2	Phase 3	Phase 4	Phase 5
Project Definition and NEPA Compliance	Final Design and Construction	Commissioning and Operations	Utilization of Secondary Use Batteries	Write Up of Demonstration Assessment
<ul style="list-style-type: none"> <li>• Update Project Management Plan</li> <li>• NEPA Compliance</li> <li>• Baseline for Evaluating Project Performance</li> <li>• Preliminary Design &amp; Planning</li> </ul>	<ul style="list-style-type: none"> <li>• Finalize Design of CES System</li> <li>• CES System Design for Project</li> <li>• Planning, Measuring, Architecture and Algorithms</li> <li>• Creation of Dispatch Algorithms</li> <li>• Communications and Control</li> <li>• Procurement of CES Systems for Installation</li> </ul>	<ul style="list-style-type: none"> <li>• Commissioning of Operational Functionalities</li> <li>• Field Testing of Designed CES Capabilities</li> <li>• Data Monitoring and Collection of Performance Data</li> <li>• Reporting of Data and Operation</li> </ul>	<ul style="list-style-type: none"> <li>• Integration of Secondary Use Batteries</li> </ul>	<ul style="list-style-type: none"> <li>• Write final report</li> </ul>
01/2010-05/2011	01/2011-06/2012	07/2012-12/2014	07/2013-06/2014	07/2014-12/2014



# CES – Operating Zones





# Modes of Operation

- Standby Operation Mode
  - Locally-initiated operation due to power loss or site-specific power quality issue.
  - This mode of operation pre-empts all other modes unless specifically overridden.
- Scheduled Operation Mode
  - Control is initiated by the DRSOC Hub on a pre-defined unit-specific schedule.
- Automatic Generation Control (AGC) Mode
  - Aggregate kW output is requested by the Independent System Operator (ISO). Individual units are dispatched by the DRSOC Hub at the appropriate outputs to meet the AGC set-point.
- Hub Command Mode
  - Control is initiated by an operator and dispatched on a unit-specific basis by the DRSOC Hub.
- Peak-shaving Mode
  - Units are dispatched by the DRSOC Hub to ensure that circuit ratings are not exceeded.




# Modes of Operation (Continued)

- DEW Economic & Reliability Dispatch Modes
  - Control is initiated by algorithms implemented in the DEW software package.
  - Algorithms are intended to maximize the economic potential of the unit.
  - May include running of the CES units in grid-parallel mode under normal circuit conditions.
  - Dispatching is done by the DRSOC Hub to each CES unit.
- DEW Model-Based Real Time Control
  - CES Operation Modes:
    - Normal: Economic
    - Storm: Reliability (Load Serving)
  - Objective Function:
    - Minimize Operation Cost
    - Minimize Loss
    - Maximize Load Serving Time After Outage






# CES - Communications Architecture





# DEW CES Control Module I/O






# Distribution Circuit in DEW


## Criteria for List of 50 Transformers:

- Rated at 25 or 50 kVA
- 5-10 Customers
- Max Annual kVA between 25 and 50
- Heavily loaded
- Frequent outages
- Circuit phase imbalance
- Accessibility






# Simulation Results, One CES Unit





# Simulation Results, 20 CES Units





# CES Test Plan

Testing	Test Description
Equipment/ Factory Acceptance Test	<ul style="list-style-type: none"> <li>S&amp;C will design perform a factory acceptance test for the CES equipment</li> <li>KEMA will provide an independent evaluation of initial design CES equipment.</li> </ul>
Functional Test	<ul style="list-style-type: none"> <li>KEMA will develop a test plan and witness testing that will demonstrate the CES Unit capability to provide specific fundamental functions:               <ol style="list-style-type: none"> <li>Peak shaving, volt-VAR, demand response (</li> <li>Remote communication and control of CES unit (DR SOC emulation)</li> <li>Islanding</li> <li>Respond to AGC simulated signal</li> </ol> </li> </ul>
System Test (DTE Field)	<ul style="list-style-type: none"> <li>The system test and evaluation will be performed in the field as the units are installed.</li> </ul>
Testing of Automotive Batteries for Secondary Use Application	<ul style="list-style-type: none"> <li>KEMA's KERMIT model will be used for a portion of this analysis, establishing a model that projects remaining lifetime based on vehicle usage profile)</li> </ul>
Comparative Test	<ul style="list-style-type: none"> <li>CES Unit original design test results will be compared to testing done on an identical CES Unit removed from service.</li> </ul>



# Secondary Use of EV Batteries

## *Battery Conditioning & Vehicle Durability Testing*

- **Project Activity**
  - Vehicle durability testing/battery conditioning started in June of 2011
  - Additional vehicles assigned to this program will begin durability testing later this month
- **Testing Locations for Mileage Accumulation & Battery Conditioning**
  - Chelsea Proving Grounds – Chelsea, MI
  - Arizona Proving Grounds – Yucca, AZ
  - Undisclosed Public Roads throughout North America



# Secondary Use of EV Batteries

## *Battery Conditioning & Vehicle Durability Testing*

### Beginning of Vehicle Reliability Testing

- Capacity – Verification Test
- Power pulse capability

### Quarterly

- Cumulative vehicle miles
- Number of charge cycles
- Energy per charge and charge time
- Summary of battery issues related to DOE program

### End of Automotive Useable Life – or End Vehicle Reliability Test

- Capacity – Total Available Energy
- 10 sec power pulse capability
- Total Charge / Discharge cycles
- Cumulative vehicle miles





## Future Work

- Finalize functional test plan
- Test DR-SOC communication and controls with CES unit with S&C CES control unit
- Test and validate DEW reliability and economic dispatch algorithm
- Finalize physical design of CES unit
- Begin internal CES equipment review and approval process
- Begin working with communities on site approval process