

2022 DOE OE Energy Storage Peer ReviewPresentation # 103

A collaborative effort supported by

- U.S. Dept. of Energy
- Sandia National Laboratories
- State of New Mexico

Prepared and presented by **Tony Sparks**, Project Manager

Albuquerque Public Schools

Facilities Design & Construction Dept.





APS' largest campus, largest utility bills.




Summertime electricity bills over \$50K; demand charges more than 50%.





Center of the Community





Large disadvantaged population.





Demographics

- Serves 2200 students (impacting thousands of families)
 - 14% from disadvantaged households (below Federal poverty line)
 - 99% eligible for Federal free or reduced lunch (APS average is 65%)
 - 20% English language learners
 - 28% Special education
 - On-site community health clinic

An ideal location.



Avengers Movie 2012 – Opening Scene



Nick Fury's Helicopter Arrives at Avenger's Headquarters.





Project objectives

- Charge from grid 'off-peak.'
- Deploy strategically during 'on-peak.'
- Reduce daily peak demand to below 500 kW.
- Test case for replication elsewhere in District.
- Potential for resiliency during power emergency.



Is it cost-effective?



Added PV to improve the payback



- 850 kW to optimize payback
- 2200 PV panels . . . one per student!
- Without PV 17 years*
- PV plus battery

 13 years

* Entirely dependent on utility rate structure.

Doubled project cost, but provides net savings of \$3.5 M over life of battery.





Resiliency

- Adding PV to battery storage allowed opportunity for 'islanding'
 - Conduct feasibility study to identify grid disconnect requirements. critical loads. etc.
 - Create islanding implementation plan & design
 - Pursue funding for implementation project



Many new opportunities opened up.





Tesla Mega Pack 2



Largest Tesla installation in New Mexico – 721 kW / 2884 kWh





Tesla Mega Pack 2




Available for on-site 'Learning Lab.'





PV layout



Lots of roof available; triggered significant roof repairs.





Lessons learned

- Design-Build delivery method is not typical for our Procurement Department, and presented challenges.
 - Life cycle and performance calculations must account for battery and solar degradation, as well as escalating utility rates. Budget accordingly!
 - New technology and high-production systems may pose concerns for the local utility company which could impede/delay an interconnection agreement.
 - Roof-mounted photovoltaics on existing buildings means roof condition and warranty must be examined. Be prepared for costly repairs!
 - Data collection and analysis especially by third party entities has many facets which
 must protect the interests and privacy of all parties.
 - EVERYTHING takes longer than expected...

And so many more lessons to come.





The importance of partners






- Expertise, experience
- Detailed, reliable analysis
- Many eyes, many viewpoints
- Shared financial burden



U.S. DEPARTMENT OF









A win for everybody!



